10" SQ.

6" SQ.

1. GRIND ALL CORNERS AND ALL WELDS SMOOTH.

2. PAINT ENTIRE ASSEMBLY WITH MINIMUM ONE COAT OF RUST INHIBITING PRIMER AND TWO COATS OF FINISH COLOR.

3. FINISH COLOR TO BE MISSOURI STATE UNIVERSITY STANDARD MAROON.

10"x10"x1/2" THICK BASE PLATE. PROVIDE 1" RADIUS AT CORNERS.

1-1/2" DEEP x 1-1/4" WIDE NOTCH TO RECEIVE PADLOCK "STAPLE".

3/16"

1/4" THICK PLATE

TS 6"x6"x3/16"

2" 4"

TS 4"x4"x3/16", WRAP RECESS WITH WHITE REFLECTIVE TAPE.

3/16" TYPICAL AT ALL JOINTS

3'-6"

3'-0"

TS 6"x6"x3/16"

3/16"

10"x10"x1/2" THICK BASE PLATE. CUT 2" DIAMETER DRAIN HOLE IN CENTER OF PLATE.

5"∅ SCHEDULE 40 STEEL PIPE.

PADLOCK "STAPLE" FABRICATED OF 1-1/2"x1-1/2"x3/4" THICK PLATE WITH 1/2"∅ HOLE TO RECEIVE PADLOCK. PROVIDE 1/2" RADIUS ON EXPOSED CORNERS

10"

3/16"

10"∅x1/2" THICK STEEL PLATE. INSTALL FLUSH WITH CONCRETE.

3/16"

1'-0"

CONCRETE PAVEMENT. THICKEN AT BOLLARD AS INDICATED.

1'-0"

3/16"

6"∅ SCHEDULE 40 STEEL PIPE SLEEVE

COARSE CRUSHED ROCK FOR DRAINAGE

2'-0"

REMOVABLE BOLLARD IN CONCRETE

SCALE: 3/4"=1'-0"

L:\STANDARDS\CONSTRUCTION STANDARDS\DIVISION 2 — SITE CONSTRUCTION\DWG\02821-3 REMOVABLE BOLLARD-CONCRETE.DWG 07\15\08 11:30

REVISION/CREATION DATE: 6/26/08