

Design Guidelines

Division 32 Exterior Improvements

Sodded Turf

- Grading shall eliminate rough or low areas to ensure positive drainage.
- Prior to installation remove all objectionable materials, trash, brush, weeds, and stones larger than 1" and grade as required to meet final established grades.
- Planting of sod shall be performed during March to October.
- Sodding shall not occur when soil is muddy or frozen.
- All sod shall be reviewed by University representative prior to installation and university representative reserves the right of refusal on sod deemed unacceptable.
- Sod shall be protected from exposure to wind and direct sunlight with moist burlap. Covering shall circulate air to reduce over heating.
- **Do not use straw.**
- **Regardless of availability of on site hose bibs or irrigation Contractor is responsible to water sod till substantial completion and until sod is rooted.**

Contractor must mow 1st cutting on established turf.

